BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2021-22/OW/WORK_INDENT49267

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/11/2021-22, Date: 15-12-2021

Name of Work:Improvements to roads and drains at Lakkappa layout and Hosabalu Nagara in ward No. 11, Kuvempunagara

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NAGOOR LOKANADHA REDDY ( )	
				In Figures	In Words
1	532.96	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications and directions of the Engineer in charge.	Cum	217.0	Rupees Two Hundred Seventeen Only
2	698.76	Removing and refixing stone slabs of drains and pointing in CM (1:3)complete as per specifications and directions of the Engineer in charge.	Sqm	116.0	Rupees One Hundred Sixteen Only
3	174.69	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete as per specifications and directions of the Engineer in charge.	Sqm	779.0	Rupees Seven Hundred Seventy Nine Only
4	66.99	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications and directions of the Engineer in charge.	Cum	6093.0	Rupees Six Thousand Ninety Three Only
5	127.89	Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification No. 1500, 1700, 2200. Including Cost of material, Labour, HOM complete as per specifications and directions of the Engineer in charge.	Cum	8116.0	Rupees Eight Thousand One Hundred Sixteen Only
6	7.67	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and directions of the Engineer in charge.	tonne	95125.0	Rupees Ninety Five Thousand One Hundred Twenty Five Only
7	365.4	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,complete as per specifications and directions of the Engineer in charge. (Data Rate)	Sqm	2018.0	Rupees Two Thousand Eighteen Only
8	4327.5	Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by road roller attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM of machineries complete as per specifications and directions of the Engineer in charge.	Sqm	43.4	Rupees Forty Three and Forty Paise Only
9	4327.5	Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications and directions of the Engineer in charge.	Sqm	6.6	Rupees Six and Sixty Paise Only
10	995.32	Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications and directions of the Engineer in charge.	Cum	2101.0	Rupees Two Thousand One Hundred One Only
11	4327.5	Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications and directions of the Engineer in charge.	Sqm	35.6	Rupees Thirty Five and Sixty Paise Only

N. Lokanadhareddy

Signature of Contractor

16/03

Executive Engineer

16/03

Name of Work:Improvements to roads and drains at Lakkappa layout and Hosabalu Nagara in ward No. 11, Kuvempunagara

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NAGOOR LOKANADHA REDDY ( )	
				In Figures	In Words
12	216.38	Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by smooth wheeled, vibratory & tandem rollers to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications and directions of the Engineer in charge.	Cum	7105.0	Rupees Seven Thousand One Hundred Five Only
13	4327.5	Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications and directions of the Engineer in charge.	Sqm	13.3	Rupees Thirteen and Thirty Paise Only
14	173.1	Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications and directions of the Engineer in charge.	Cum	10501.0	Rupees Ten Thousand Five Hundred One Only
15	134.6	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications and directions of the Engineer in charge.	Sqm	477.0	Rupees Four Hundred Seventy Seven Only

N. Lokanadha Reddy
Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
16/03

16/03